

الجامعة السلامية العالمية عاليريا INTERNATIONAL ISLAMIC UNIVERSITY MALAYSIA ويُنبَونِنَونِنَونَالِمُ انْبَارَا نِجْنَا مِلْسِنَا

A PRELIMINARY EVALUATION OF PREFABRICATED BATHROOM FOR HIGH-RISE HOUSING SCHEMES IN MALAYSIA

BY

ZULKEFLE BIN ISMAIL

INTERNATIONAL ISLAMIC UNIVERSITY MALAYSIA

2007

A PRELIMINARY EVALUATION OF PREFABRICATED BATHROOM FOR HIGH-RISE HOUSING SCHEME IN MALAYSIA

BY

ZULKEFLE BIN ISMAIL

A thesis submitted in fulfilment of the requirement for the degree of Master of Science (Built Environment)

Kulliyyah of Architecture and Environmental Design International Islamic University Malaysia

MAY 2007

ABSTRACT

The main objectives of this research are to investigate the significant factors of the implementation of prefabricated bathroom as part of Industrialized Building System (IBS), and the relationship between quality, cost and productivity. The preliminary idea to this research come from the national aspiration of Vision 2020 that is to transform and industrialized the Malaysian construction industry. The evolution of industrialization from craftsmanship into a developed process that eventually evolved to the production of bathroom is highlighted. A system architecture, which takes advantage of new technology, could change the entire construction industry. Most of housing industry in developing countries did not take the advantage of advancement in manufacturing industry especially the implementation of Industrialized Building System (IBS) such as prefabricated bathroom. Factory-manufactured components for example the prefabricated bathroom are easy to assembled on-site, use less labour, faster to construct and it has a high quality which will add value to the houses. The methodology used in this study are questionnaire, semi-structured interviews and observation. They are used to identify the status of implementation of prefabricated bathroom in Malaysia. The findings identified that architects and engineers tend to reject the implementation of prefabricated bathroom in Malaysia. The needs to cut cost and improvement in quality of prefabricated bathroom will give a greater drive to its usage in construction sites and achieved customer's satisfaction. implementation of prefabricated bathroom could help to reduce construction time and site labour. It will also relieve the labour crisis, improved quality while keeping cost reasonable. Further development in prefabrication will also leads to closer integration between building services and manufacturing engineering without compromising the users preference. As a conclusion, to achieve the customer's needs and satisfaction, design guidelines need to be developing as a standard for construction practice in order to enhance the usage of prefabricated bathroom in Malaysia. The Malaysia government should play a greater role in exposing and encouraging the construction industry and the public to the next generation of prefabricated bathroom design and technology.

ملخص البحث

تتمثل الأهدافَ الرئيسة لهذا البحثِ في فحص العناصر الهامّة لأدوات الحمّامِ الجاهز كجزء مِنْ نظام المبانى الصناعية (IBS)، وعلاقتها بين المظاهر العامّةِ للنوعيةِ والتكلفة ولمعدل الإنتاج. والفكرة المبدئية لهذا البحثِ تتمثل في الطموح الوطني مِنْ رؤيةِ 2020 الذي يسعى إلى تحويل وتصنيع أعمال المباني الماليزية. وأصبح ارتقاء التصنيع من الحرفة إلى مرحلة التشييد المتطور بارزا من ناحية الابتكار الجديد للحمام السكني. وباستطاعة النظام المعماري المطبق على التكنولوجيا الجديدة أن يغير التصنيع البنائي بأكمله. أغلب الصناعات السكنية في الدول الناميةِ لمْ تنتهز فرص التقدّم الصناعي وخاصة من الناحية التطبيقية لنظام المباني الصناعية (IBS) مثل الحمّام الجاهز. الأجزاء المركبة التي تصنعها المصانع مثل أدوات الحمّامات الجاهزة تركب بسهولة في مواقع البناء، وتحتاج إلى قليل من العمال إلى جانب سرعة الإنجاز والنوعية العالية والتقنية المتقدمة وكذلك زيادة في القيمة السكنية. المنهجيات المستخدمة لإجراء هذه الدراسة تتضمّنُ الإستفتاء، والمقابلات والملاحظات لتَمييز الطبيعة التطبيقية للحمّام الجاهز في ماليزيا. توصلت النتائج إلى أن المهندسيين والمعماريين يميلون إلى رفض الأدوات المستعملة للحمام الجاهز في ماليزيا. والحاجات إلى تخفيض الثمن وتحسين النوعية لأدوات الحمام الجاهز ستعطى حيوية رفيعة في استخدامها في بناء القطع الأرضية وإرضاء الزبائن. وتصنيع الأدوات للحمام الجاهز سيساعد في تقليل زمن البناء وتسهيل العمل على القطعة الأرضية. كما أنه سيخفف في أزمة العمل، ويحسن النوعية إلى جانب السعر المعقول. وسيُؤدّى التطور المستمر في هذا التصنيع إلى تكامل أقرب بين خدمات البناء والهندسة الصناعيةِ من دون شبهة في إرضاء المستخدمين. وفي الخلاصة نتلمس ضرورة إيجاد كل ما يحتاج إليه الزبائن ويرضونه وذلك عن طريق التخطيط لحَلِّ مشاكل التصميم وتطوير دليله كمعيار ممارسة البناء نحو تحسين الحمّاماتِ الجاهزة في ماليزيا. وعلى الحكومة الماليزية أن تؤدي دورا كبيرا في عرض وتشجيع التصنيع البنائي للجيل القادم في التصميم والتكنولوجيا الجديدة لأدوات الحمام الجاهز

ABSTRAK

Objektif utama penyelidikan ini adalah untuk mengkaji faktor-faktor yang signifikan di dalam pelaksanaan bilik air pasang siap yang merupakan sebahagian daripada Sistem Binaan Berindustri (IBS) dan hubungannya dengan aspek-aspek kos, kualiti dan produktiviti. Aspirasi nasional Wawasan 2020 untuk merubah dan memajukan sector pembinaan negara ke arah berindustri menjadi idea awal penyelidikan ini. Evolusi perindustrian dari kerja-kerja ketukangan kepada proses pembangunan yang akhirnya berkembang hingga ke peringkat pengeluaran bilik turut diketengahkan. Senibina sistem yang memanafaatkan teknologi terkini dapat menukar seluruh industri pembinaan. Kebanyakan negara-negara sedang membangun kurang memanafaatkan kelebihan industri pembuatan Sistem Binaan Berindustri (IBS) terutamanya di dalam pelaksanaan bilik air pasang siap di dalam industri pembinaan mereka. Komponen yang dikilangkan seperti bilik air pasang siap mudah dipasang, menggunakan kurang pekerja, lebih cepat dibina dan ianya berkualiti tinggi di mana akan menambahnilai bangunan kediaman. Kaedah penyelidikan ini ialah borang kaji selidik, temuduga separa berstruktur, dan pemerhatian. Ianya telah dijalankan bagi mengenalpasti status pelaksanaan bilik air pasang siap di Malaysia. Hasil penyelidikan mendapati arkitek dan jurutera bangunan lebih cenderung kepada menolak pelaksanaan bilik air pasang siap di Malaysia. Keperluan mengurangkan kos serta meningkatkan kualiti bilik air pasang siap akan memberi daya penggerak yang besar terhadap penggunaan yang meluas di tapak pembinaan serta mencapai kepuasan pelanggan. Pelaksanaan bilik air pasang siap telah dikenalpasti dapat membantu mengurangkan masa pembinaan dan penggunaan tenaga buruh di tapakbina. Ini juga akan dapat mengurangkan krisis buruh, meningkatkan kualiti disamping mengekalkan kos yang munasabah. Pembangunan kaedah pasang siap akan membawa kepada integrasi yang baik antara bangunan dan kejuruteraan pembuatan tanpa mengkompromi kecenderungan pengguna. Kesimpulannya, untuk memenuhi kehendak dan kepuasan pelanggan, garis panduan rekabentuk haruslah dibentuk sebagai piawaian untuk amalan pembinaan untuk meningkatkan penggunaan bilik air pasang siap di Malaysia. Kerajaan Malaysia perlu memainkan peranan menggalakkan orang ramai dan industri pembinaan negara kepada teknologi dan rekabentuk terkini bilik air pasang siap.

APPROVAL PAGE

I certify that I have supervised and read this study and that to acceptable standards of scholarly presentation and is find quality, as a thesis for the degree of Master of Science (But	fully adequate, in scope and
	Asiah Abdul Rahim Supervisor
	Syed Tauseef Ahmad Co-Supervisor
I certify that I have read this study and that in my opinion standards of scholarly presentation and is fully adequate thesis for the degree of Master of Science (Built Environment)	, in scope and quality, as a
	Maisarah Ali Internal Examiner
	Taksiah A. Majid External Examiner
This thesis was submitted to the Department of Archite fulfillment of the requirement for the degree of Environment).	
	Zuraini Denan Head, Department of Architecture
This thesis was submitted to the Kulliyyah of Architecture and is accepted as a fulfillment of the requirement for the (Built Environment).	
	Mansor Ibrahim Dean, Kulliyyah of Architecture

DECLARATION

I hereby declare that this dissertation is the result	of my own investigations, except
where otherwise stated. I also declare that it has n	not been previously or concurrently
submitted as a whole for any other degrees at IIUM	or other institutions.
Zulkefle bin Ismail	
Signature	Date

INTERNATIONAL ISLAMIC UNIVERSITY MALAYSIA

DECLARATION OF COPYRIGHT AND AFFIRMATION OF FAIR USE OF UNPUBLISHED RESEARCH

Copyright © 2007 by Zulkefle Ismail. All rights reserved.

A PRELIMINARY EVALUATION OF PREFABRICATED BATHROOM FOR HIGH-RISE HOUSING SCHEMES IN MALAYSIA

No part of this unpublished research may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording or otherwise without prior written permission of the copyright holder except as provided below.

- 1. Any material contained in or derived from this unpublished research may only be used by others in their writing with due acknowledgement.
- 2. IIUM or its library will have the right to make and transmit copies (print or electronic) for institutional and academic purposes.
- 3. The IIUM library will have the right to make, store in a retrieval system and supply copies of this unpublished research if requested by other universities and research libraries

Affirmed by Zulkefle Ismail.	
Signature	Date

In the name of God, Most Gracious, Most Merciful


"By (the Token of) Time (through the Ages), Verily Man is in loss,

Except such as have Faith, and do righteous deeds, and (joint together)

in the mutual teaching of Truth, and of Patient and Constancy."

(Qur'an, Al 'Asr: 1 – 3)

ACKNOWLEDGEMENTS



Al-salam'alaykum warahmatullah

Alhamdulillah, praise to Allah, the Most Gracious and Most Merciful. With His blessing, this research can be completed despite the various constraints encountered. Firstly, I would like to express my deepest gratitude to my supervisors, Assoc. Prof. Ar. Dr. Asiah Abdul Rahim (main supervisor) and Assoc. Prof. Dr. Syed Tauseef Syed Ahmad (co-supervisor) for their patience and their useful comments as well as comprehensive and bright ideas that have guided me in writing this thesis from the beginning until the end.

I also would like to express my special thanks to Assoc. Prof. Dr. Saodah Wok from Kulliyyah of Islamic Reveal Knowledge and Human Sciences (IRKHS) and Mr. Azman Abu Talib from Centre for Language Pre-University Academic Development (CELPAD) and for their guidance in terms of research methodology, data analysis and proofreading.

I also would like to express my thanks to:

- All staff of Dar Al Hikmah Library and Kulliyyah of Architecture and Environmental Design (KAED) Resource Center of International Islamic University Malaysia, Kuala Lumpur.
- Construction Industry Development Board (CIDB) of Malaysia, Housing Development Board (HDB) and Building and Construction Authority (BCA) of Singapore.
- Ministry of Higher Education, Malaysia and Politeknik Sultan Haji Ahmad Shah (POLISAS), Kuantan, Pahang Darul Makmur for my study leave and sponsored the study.
- My own brother, Zabidi Ismail, Resident Engineer of DBKL Linear City 2 Public Housing Project, Kuala Lumpur for his support and assistance
- All KAED's staffs, especially Asst. Prof. Dr. Ahmad Shukri Yusof, Asst. Prof. Dr. Abdul Razak Sapian, Assoc. Prof. Dr. Spahic Omer and Asst. Prof. Dr. Puteri Shireen Jahn Kassim for their helps and assistance.
- Assoc. Prof. Ar. Dr. Ku Azhar Ku Hassan, Bro. Wan Burhanuddin Wan Abidin and Assoc. Prof. Dr. Ahmad Sanusi Hassan from School of Housing Building and Planning (HBP) Universiti Sains Malaysia (USM) Penang and Assoc. Prof. Dr. Ahmad Fauzi Abdul Wahab from Faculty of Built Environment, Universiti Teknologi Malaysia (UTM) for their personal views and ideas about this research
- Lastly, to my beloved parents, siblings and family, especially Mrs. Junaida Shaari and sons, Zull-Fareezal Bukhari Zulkefle and Zull-Firdaus Hanaffi Zulkefle at Ipoh, Perak Darul Ridzuan for their support and dua'

"Syukran Jazilan" to all. May Allah shower us with His Blessings and Love and living in the path of Islam. Amin.

TABLE OF CONTENTS

Abstract		ii	
Abstract in Arabic	Abstract in Arabic		
Abstract in Bahasa Malaysia			
Approval Page		V	
		vi	
		vii	
Dedication		viii	
Acknowledgemen	nt	ix	
List of Tables		X	
List of Figures		хi	
CHAPTER ONE:	: INTRODUCTION		
1.0 The Cu	Surrent Situation	1	
1.1 The Re	esearch Goal and Objectives	2	
	nent of the Problem	4	
	esearch Hypothesis	6	
	Ficance of the Study	7	
_	nary	8	
	~ · · · · · · · · · · · · · · · · · · ·		
CHAPTER TWO): LITERATURE REVIEW		
2.0 Introduction			
	cating Architecture	10	
	trialized Building System (IBS) in Malaysia	14	
2.2.1		15	
2.2.2	Classification of Industrialized Building System (IBS)	15	
2.2.3	Relationship of IBS With Other Systems	21	
2.3 Prefab	pricated Bathroom	23	
2.3.1	Design Concept	24	
2.3.2	Type of Materials	31	
	2.3.2.1 Fibre Reinforced Concrete (GRC)	31	
	2.3.2.2 Fibre Reinforced Plastic (FRP)	32	
	2.3.2.3 Composite Panels: Fibre Glass Sandwich Panels	35	
	2.3.2.4 Steel Sandwich Panels.	37	
2.3.3	Benefits	38	
2.3.4	Operational Concept	39	
2.3.5	Experience of Prefabricated Bathroom in USA, UK and HK	42	
2.5.5	2.3.5.1 United States of America (USA)	42	
	2.3.5.2 Hong Kong (HK)	45	
	2.3.3.3 United Kingdom (UK)	50	
2.3.4		52	
2.3.4	Summary	JL	

CHAPTER THRE	EE: RESI	EARCH METHODOLOGY	
3.0 Introdu	uction		53
3.1 Key R	esearch C	Concept and Assumption	53
3.2 Resear	ch Appro	ach	55
3.3 The Ro	esearch D	esign	57
3.3.1	Method	of Data Collection	57
	3.2.1.1	The Questionnaire	59
	3.2.1.2	Semi-Structured Interview	62
	3.2.1.3	Unstructured Observation – Factory Visit	64
3.3.2	Method	of Data Analysis	64
3.4 Operat	tionalizat	on	66
3.5 Pilot T	est		67
3.6 Summ	ary		68
		RPRETATION AND ANALYSIS OF DATA	
			69
4.1 Quanti		alysis of Questionnaire Survey	70
4.1.1		ty of the Data	70
4.1.2		eristic of the Respondents	71
4.1.3		rent Position of IBS	72
		The Familiarity of IBS	72
	4.1.3.2	The Usage of IBS	73
	4.1.3.3	Type of Project Undertaken by Respondents	74
	4.1.3.4	Popular Type of Construction by Respondents	76
4.1.4		vantages and Disadvantages of Prefab Bathroom	78
4.1.5		ther Opinion in Implementing of Prefab Bathroom	86
	4.1.5.1	The Acceptance to Implement Prefab Bathroom	87
	4.1.5.2	The Future Usage of Prefab Bathroom	88
	4.1.5.3	The Technology of Prefab Bathroom	90
	4.1.5.4	The Customers' Satisfaction on Prefab Bathroom	92
	4.1.5.5	The Future Development of Prefab Bathroom	95
4.1.6		Opinion on Prefabricated Bathroom	99
		The Role of Local Authority Control Departments	100
	4.1.6.2	The Problems of Prefabricated Bathroom	100
	4.1.6.3	Cost of Prefabricated Bathroom	102
	4.1.6.4	Quality of Prefabricated Bathroom	103
_		alysis of Interview and Observations	103
4.2.1		ers' Satisfaction	104
	4.2.1.1	Warranty and Certification	104
	4.2.1.2	Performance and Maintenance	105
	4.2.1.3	Technology and Innovation	107
	4.2.1.4	Reduction of Cost	111
	4.2.1.5	Physical Strength	112
400	4.2.1.6	Quality Product	113
4.2.2		nal Requirement	114
	4.2.2.1	High Quality Materials	114
	4.2.2.2	Ease of Assembly	115
	4.2.2.3	Reduction of Site Labour	118
	4.2.2.4	Technology Transfer	118

CHAPTER FOUR: INTERPRETATION & ANALYSIS OF DATA (continue)	
4.2.3 Physical Form	119
4.2.3.1 Eastern Pretech	119
4.2.3.2 Hong Leong Asia Ltd	125
4.2.3.3 Matsushita Electric Works Pte. Ltd	127
4.3 Design Strategy	129
4.4 Summary	131
CHAPTER FIVE: CONCLUSION AND RECOMMENDATION	
5.0 Introduction	
5.1 Conclusion	132
5.2 Future Research	132
	136
BIBLIOGRAPHY	137
APPENDIX A: Questionnaire	144
APPENDIX B: Semi-structured Interview	148
APPENDIX C: Unstructured Observation – Factory Visit	149
APPENDIX D: Paper Presented at University of Malaya, Kuala Lumpur	180
APPENDIX E: Paper Presented at UTC Hanoi, Vietnam	190

LIST OF TABLES

Title N	<u> Title No.</u>	
3.1	Comparison Between a Qualitative and Quantitative Method	56
4.1	Reliability Analysis – Scale (Alpha)	71
4.1	The Pull and Push Factor of Implementing Prefabricated Bathroom in Malaysia	83
4.2	The Pull and Push Factor of Implementing Prefabricated Bathroom in Singapore	86
4.4	The Summary of Statistical Analyses of Costumer Satisfaction, Functional Requirements, and Physical Form for Respondents in Malaysia	98
4.5	Personal Opinion of Prefabricated Bathroom for Malaysia and Singapore	99

LIST OF FIGURES

<u>Title</u>	<u>Title No.</u>	
1.1	The Intersection between Industrialized Building System (IBS) for Prefabricated Bathroom and Construction Players	4
1.2	Hypothesis Flow Chart	6
2.1	Vanity in Prefabricated Bathroom	10
2.2	Bison Wall-Frame System (1962), United Kingdom (UK)	12
2.3	Prototype of Modular Service System	13
2.4	Skeletal Frame System	17
2.5	Load Bearing Wall Panel System	17
2.6	Cell or Box System	18
2.7	Steel Formwork System	18
2.8	Steel Framing System	19
2.9	Prefabricated Timber Framing System	19
2.10	Dry Building Method: Blockwork	20
2.11	Relationship of Industrialized Building System (IBS) With Other Systems	22
2.12	Design of Prefabricated Bathroom in Asia and Europe	25
2.13	Example of Design of Prefabricated Bathroom from United Kingdom (UK)	27
2.14	Design Development of Two Basic Design of Prefabricated Bathroom in Germany	27
2.15	Example Design of Prefabricated Bathroom from France: Rectangular and Curvilinear Shape	28
2.16	The Design Concept of Prefabricated Bathroom	29

Title 1	<u>No.</u>	Page No
2.17	Glassfibre Reinforced Concrete (GRC) Bathroom Slab	32
2.18	The Detail Section of Glafiba Prefabricated Bathroom's Standard Floor Panel.	33
2.19	The Detail Section of Glafiba Prefabricated Bathroom's Wall Panel	34
2.20	The Detail Section of Glafiba Prefabricated Bathroom's Joints between the Panels and between Pavement and Walls	34
2.21	The Interior and Plan View of Fibre Glass Sandwich Panel of Grumbach Prefabricated Bathroom from Germany	36
2.22	The Exterior of Steel Sandwich Panel of Deba Prefabricated Bathroom from Germany	37
2.23	The Single Function of Atoll and Hydra Model of Prefabricated Bathroom from France	40
2.24	The Dual Function of Riviera and Therma Model of Prefabricated Bathroom from France	40
2.25	The Triple Function of Floréane and Oasis Model of Prefabricated Bathroom from France	41
2.26	The Proposed Prefabricated Bathroom for Cornell University, the United States of America (USA)	43
2.27	The Component Diagrams of Proposed Prefabricated Bathroom for Cornell University	44
2.28	Floor Plan of Typical Bathroom Unit at Tseung Kwan O Area 73A (Phase 2)	46
2.29	Lifting and Loading Test of Prefabricated Bathrooms in the Factory	48
2.30	Installation and Pressure Test for Water Supply Pipe of Mock-up Prefabricated Bathroom	49
2.31	Pilot Project of Prefabricated Bathroom at Tseung Kwan O Area 73A (Phase 2) of the Hong Kong Housing Department.	50
2.32	Italian Technology of European Ensuite Prefabricated Bathroom for the University of Hertfordshire, United Kingdom (UK)	51
3.1	The Research Concept Chart	54

Title N	No. Paş	ge No
3.2	The Research Approach Chart	57
3.2	The Research Strategy Flow Chart	54
3.3	Method of Data Collection: Triangulation	58
3.4	The Research Design: Relationship of Data Collection and Data Analysis	66
3.5	The Dependent and Independent Variables of Research	66
4.3	Characteristic of the Respondents	71
4.2	The Popularity of Industrialized Building System (IBS) Among Architect and Engineer in Malaysia and Singapore	72
4.3	The Usage of Industrialized Building System (IBS) Among Architect and Engineer in Malaysia and Singapore	73
4.4	Type of Project Undertaken by Architect and Engineer from Malaysia and Singapore	75
4.5	Popular Type of Construction Used by Architect and Engineer in Malaysia and Singapore	77
4.6	The Advantages of Using Industrialized Building System (IBS) by Architect and Engineer in Malaysia and Singapore	79
4.7	The Barriers in Implementing Industrialized Building System (IBS) for Bathrooms by Architect and Engineer in Malaysia and Singapore	81
4.8	The Factors Requiring for Further Implementation of Prefabricated Bathrooms by Architect and Engineer in Malaysia and Singapore	84
4.9	The Statistics (Malaysia and Singapore) of the question "Do you agree to implement prefabricated bathroom in your house"	87
4.10	The Statistics (Malaysia and Singapore) of the question "The usage of prefabricated bathroom will play a role now and future"	88
4.11	The Statistics (Malaysia and Singapore) of the question 'the usage of prefabricated bathroom will increase over the next three years'	89
4.12	The Statistics (Malaysia and Singapore) of the question 'Transition of technology from handcraft to machine-craft for bathroom production will be increased in our building industry'	90

<u>Title</u>	<u>No.</u>	Page No.
4.13	The Statistics (Malaysia and Singapore) of the question 'integrated of new component and innovation of materials for bathroom's floor and wall'	91
4.14	The Statistics (Malaysia and Singapore) of the question 'the prefabricated bathroom enables to provide higher levels of customer satisfaction'	92
4.15	The Statistics (Malaysia and Singapore) of the question 'the installation of flexible and adjustable hose pipe for water supply should be provided for easy use'	93
4.16	The Statistics (Malaysia and Singapore) of the question 'users are demanding the variation, quality enhancement and choices of prefabricated bathroom'	94
4.17	The Statistics (Malaysia and Singapore) of the question 'research is important to explore, exploit and enhance new materials and innovation of bathroom'	95
4.18	The Statistics (Malaysia and Singapore) of the question 'a standard design guideline of bathroom will enhance the quality and performance of bathroom's installation'	96
4.19	The Detail Section of Conventional Floor Trap and New "Shallow' Floor Trap.	106
4.20	Prefabricated Bathroom of HDB's Prefabricatation Technology Centre in Toa Payoh Public Housing, Singapore	107
4.21	Precast Concrete Prefabricated Bathroom Completed With Finished Wall and Floor Prior to Delivery to Site	108
4.22	Wall Panel and Floor Tray Prefabricated Bathroom Pre-Assembled in Factory Prior to Delivery to Site	109
4.23	Wall Panels and Floor Tray Prefabricated Bathroom Separately Lifted and Assembled at Site	110
4.24	Installation of Prefabricated Bathroom (Wall Panel and Floor Tray Pre-Assembled in Factory) to High-Rise Residential Building in Singapore	116
4.25	Four Models of Prefabricated Bathroom	120
4.26	Models of Parma 1 Prefabricated Bathroom that Produce by Eastern Pretech	121

Title 1	<u>Pag</u>	
4.27	Parma 1: Specification	123
4.28	Parma 1: Interior Finishes	124
4.29	Interior and Exterior View of prefabricated bathroom by Hong Leong Asia Ltd	126
4.30	Isometric Component Detail View of National Prefabricated Bathroom	m 128

CHAPTER ONE

INTRODUCTION

This study investigates the factors and analyses the prospect of implementing prefabricated bathroom in Malaysia. The implementation of Industrialized Building System (IBS) in Malaysia and issues surrounding construction industry are discussed. This chapter starts with the background of the study, a brief review of the nature of problems, aims and objectives, scope of the study, overview of methodology and the significance of the study.

1.0 THE CURRENT SITUATION

The needs for Malaysian construction industry to be competitive in the emerging global economy are crucial. Industrialization of high-rise residential building components is critical in order to be competitive. Besides new trend in design and construction, the high demand on housing due to increasing population makes the high-rise housing the best alternative to solve the housing problem given the limited space for such development especially in the city.

According to Construction Industry Development Board (CIDB), Malaysian construction industry is currently facing problems due to poor site condition, too much dependency on foreign workers, low productivity, poor quality, and high wastage. Some construction players have responded to this crisis by adopting prefabrication system i.e. Industrialized Building System (IBS) and by building a more uniform product (CIDB, 2005).

According to Thomas (2005), prefabricated bathroom is becoming more popular in some developed countries. It has become an important and cost effective concept in today's fast track construction culture (Percival, 2005; Ballard and Arbulu, 2004; Gibb, 1999; Bottom, et al., 1996). Prefabrication techniques transform some of the construction process to a controlled factory environment. A more uniform product has slightly increased the quality of bathroom and decreased the amount of learning required to construct a bathroom. However, bathroom manufacturers are still unable to provide a high quality bathroom or reduce the cost and time of manufacturing.

According to Sebestyén (1998), the efficiency in manufacturing give prefabricated bathroom a good reputation which is good for future development of its technology and innovation. Unfortunately, poor joint design and component integration have resulted in leakages that give negative image to the prefabricated bathroom in Malaysia (Chan, 2005). Therefore, there is a need to explore and enhance the present technology of prefabricated bathroom.

1.1 THE RESEARCH GOAL AND OBJECTIVES

The goal of this research is to evaluate and to determine the impact of the application of prefabricated bathroom in Malaysia's construction industry. To address this goal, the research explores the benefits and advantages of prefabrication to construction industry, the requirements for its implementation, the factors to be considered in developing Industrialized Building System (IBS), and its maintenance. The characteristics of Singapore's construction industry and the contributing factors that lead to their success in implementing the prefabricated bathroom to their high-rise residential building are studied.

The Joint Committee on Standards for Educational Evaluation (1994) defined evaluation as "systematic investigation of the worth or merit of an object." Accordingly, evaluation should be conducted for action-related reasons, and the information provided should facilitate the decision on course of action.

Evaluation was used firstly because evaluation provides information to help improve the research. Information on whether goals are being met and on how different aspects is working and essential for continuous improvement process. Secondly, evaluation provides information for communicating construction industry players. It allows research to enhance the analysis of the study and test the research hypothesis. In this study, the evaluation of prefabricated bathroom is based on observation, questionnaires and interviews.

A survey was conducted on the construction players to determine the success of implementing prefabricated bathroom in their project. Interviews were conducted to find out the problems and issue during its implementation. Finally, this research will come up with pertinent findings and recommendations on prefabricated bathroom implementation in Malaysia.

As a summary, the main objectives of this research are:

- To investigate the significant factors of implementing prefabricated bathroom as part of Industrialized Building System (IBS), and
- To investigate the relationship between quality, cost, design, and construction process of prefabricated bathroom.

1.2 STATEMENT OF THE PROBLEM

The research problems were identified in three (3) areas. The first area is Industrialized Building System (IBS) as a new construction system in Malaysia which is elaborated in Chapter 2. The second area is a subset of the first, which is prefabricated bathroom for high-rise residential buildings. This is discussed further in Chapter 2. The third area is construction players, who are the key-persons from who data is obtained. This is discussed further in Chapter 3. The intersection of these three areas is shown below in Figure 1.1:




Figure 1.1: The intersections between Industrialized Building System (IBS) for Prefabricated Bathroom and Construction Players.

Most of the buildings in Malaysia are built in a craft manner almost the same way, as it was constructed hundred years ago. This lack of improvement in the construction process has severely limited the industry's ability to improve its product. According to Lawrence (2003), the cost of high-rise housing has continually risen, while the quality has fallen. Resources and labour have become more expensive, and the inefficient craft system is not well equipped to deal with these problems. According to CIDB (2003), IBS Roadmap 2003-2010 aims to reduce the dependency on foreign workers in stages from 75% in 2003 to 55% in 2005 and 15% in 2009. Lawrence (2003) claimed that on-site labour could account for up to 80% of the cost while only 20% is spent on materials produced off-site.

In a forum at Construction Industry Development Board (CIDB) key issues of prefabricated bathroom in order to create high-value housings have been raised. Two questions on the implementation of prefabricated bathroom were raised in this forum:

- How to develop prefabricated bathroom related to design, products (quality and cost), technologies (construction) and services (maintenance) for buildings?
- How to introduce the industry and public to the next-generation of prefabricated bathroom design and technology?

It is important to note that prefabricated bathroom is not a 'standard building modules', but it is used to achieve a variety of designs at reduced cost. The consumer demands personalized solutions, which are too expensive to be provided unless the manufacturers offer various designs of prefabricated bathrooms. The consumers also want to be able to modify their bathroom when their needs increased or according to their satisfaction. Therefore, the prefabricated bathroom should offer quality and variety in designs at a reasonable cost.